

TUMKUR DIVISION.

ADVERTISEMENT.

The 28th November 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 1st January 1888, for restoring the Handenhalli Tank, Sira Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Handenhalli Tank, Sira Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed Abstract Estimate of restoring Handenhalli Tank, Registered
No. of Sira Taluk.

Items of Work.				Per.	Quantity.	Rate.	Cost.
<i>Bund.</i>							
Earthwork	..	..	..	C. Yd.	131,394		
New stone work	..	..	..	do	6,257		
Old stone work	..	..	..	do	2,275		
Bench Mark stones	..	..	..	Each.	2		
Grade stones	..	..	..	do	41		
Excavation	..	..	..	C. Yd.	2,625		
Total..				..	..		
<i>Sluices.</i>							
2 Sluices	..	..	..	L. S.	1,000		
<i>Waste Weir.</i>							
Excavation	..	..	..	C. Yd.	20,000		
Brick in chunam	..	..	..	C. Ft.	14,087		
Chunam plastering	..	..	..	Sq.	37.52		
Covering slabs	..	..	..	S. Ft.	938		
Total....				..	..		
<i>Distribution.</i>							
Sluice channel on both sides	..	..	..	L. S.	5,000		
<i>Miscellaneous.</i>							
Compensation of lands submerged..	..	..	..	..	1,514		

C. T. DALAL,
Executive Engineer.